

Project Name	Project Name
Client Name :	ABC Construction
Job No :	100
Delivery Address :	43 Golden Drive
Suburb :	
Date :	29.08.2022

FASCIA PURLIN

Item	Description	Assembly Mark	Part Mark	Colour	Qty	Length(mm)	Gross Weight (Kg)	Comments
FASCIA PURLIN	C20015	A/16	FP/1	C450L0	4	7250.00	32.00	
FASCIA PURLIN	C20015	A/30	FP/2	C450L0	8	7000.00	30.00	
Subtotal					12	85000.00	370.32	

PURLIN

Item	Description	Assembly Mark	Part Mark	Colour	Qty	Length(mm)	Gross Weight (Kg)	Comments
PURLIN	C20015	p/5	M/1	C450L0	11	7250.00	32.00	
PURLIN	C20015	p/6	M/2	C450L0	54	6998.00	30.00	
PURLIN	C20015	p/7	M/3	C450L0	1	7249.10	32.00	
PURLIN	C20015	p/7	M/3	C450L0	1	7249.50	32.00	
PURLIN	C20015	p/7	M/3	C450L0	2	7250.00	32.00	
PURLIN	C20015	p/7	M/3	C450L0	6	7250.10	32.00	
PURLIN	C20015	p/8	M/4	C450L0	11	7250.00	32.00	
PURLIN	C20015	p/10	M/5	C450L0	34	6998.00	30.00	
PURLIN	C20015	p/11	M/6	C450L0	11	7250.00	32.00	
PURLIN	C20015	p/12	M/7	C450L0	1	7250.00	32.00	
Subtotal					132	934823.00	4072.79	

SIDEWALLGIRT

Item	Description	Assembly Mark	Part Mark	Colour	Qty	Length(mm)	Gross Weight (Kg)	Comments
SIDEWALLGIRT	C15015	p/4	M/11	C450L0	16	7262.00	25.00	
SIDEWALLGIRT	C15015	p/9	M/12	C450L0	32	6998.00	24.00	
SIDEWALLGIRT	C15015	p/3	M/13	C450L0	2	8607.66	30.00	
SIDEWALLGIRT	C15015	p/2	M/14	C450L0	4	8542.34	30.00	
SIDEWALLGIRT	C15015	p/18	M/15	C450L0	4	8542.34	30.00	
SIDEWALLGIRT	C15015	p/17	M/16	C450L0	1	8454.66	29.00	
SIDEWALLGIRT	C15015	p/16	M/17	C450L0	1	8607.66	30.00	
SIDEWALLGIRT	C15015	p/19	M/18	C450L0	1	8453.66	29.00	
SIDEWALLGIRT	C15015	p/19	M/18	C450L0	1	8454.66	29.00	
SIDEWALLGIRT	C15015	p/1	M/19	C450L0	2	8607.66	30.00	
Subtotal					64	476868.00	1658.33	
Total					208	1496691.19	6101.45	